

ENGINEERING DEPARTMENT.

MYSORE DIVISION.

Dated 1st October 1927:

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division up to 29th October 1927 for constructing a Local Fund Dispensary at Kagalwadi, Chamrajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed or it may be stated how much less than the sanctioned amount in terms of percentage the work will be undertaken:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a Local Fund Dispensary at Kagalwadi, Chamrajnagar," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Orders to execute the work will be issued only after the full cost of the estimate is recovered from the Deputy Commissioner and the successful tenderer should bind himself to take up the work at the rates tendered and accepted. No claim for any enhanced rates will be entertained on account of any delay and if in case the full amount of the estimate is not recovered orders to start the work issued within 31st January 1928, the earnest money will be refunded.

Abstract estimate for constructing Local Fund Dispensary at Kagalwadi, Chamrajnagar Taluk.

No.	Items of work	Quantity	Per	Rate	Cost
	<i>Dispensary Building.</i>			Rs. a. p.	Rs.
1	Earthwork excavation ...	74	C.yd.	0 4 0	18
2	Brick in clay ...	5,005	C.ft.	0 3 6	1,095
3	Brick in mortar arch work ...	99	"	0 8 0	50
4	Burnt stone slabs 6" thick dressed ...	353	S.ft.	0 12 0	265
5	Cut stone pillars with capitals and bases, complete.	10	Each	30 0 0	300
6	Masonry mouldings at ends ...	2	"	4 0 0	8
7	Plastering in mortar ...	39.38	Sqr.	4 0 0	158
8	Whitewashing ...	23.39	"	0 5 0	7
8a	Colour washing ...	15.91	"	0 6 0	6
9	Teakwood pannelled doors (without bottom rails) hinges, etc., complete.	126	S.ft.	2 4 0	283
10	Teakwood pannelled windows with wooden shutters including iron bars $\frac{3}{4}$ " dia. with iron fittings, hinges, etc., complete.	82	"	3 4 0	236
11	Ventilators with glazed shutters ...	27	"	2 0 0	54
12	Circular ventilators ...	13	"	3 8 0	46

No.	Items of work	Quantity	Per	Rate	Cost
<i>Dispensary Building—concl'd.</i>					Rs. a. p. Rs.
13	Jungle wood work wrought and put up	106.25	C.ft.	4 8 0	478
14	Roofing with first class Mangalore tiles over teak reepers, etc., complete.	19.20	Sqr.	35 0 0	672
15	Ridge tiles set in mortar and cement pointing.	80	R.ft.	0 10 0	50
16	Zinc sheets for valleys	44	S.ft.	1 4 0	55
17	Teakwood plant $\frac{1}{2}$ " thick	44	"	0 8 0	22
18	Eave board 9" high ornamental	262	R.ft.	0 12 0	197
19	Cornice 3" complete	25	"	0 8 0	13
20	Wood oiling two coats	18.15	Sqr.	3 0 0	54
21	Chocolate painting	10.21	"	5 0 0	51
22	Teakwood finials	4	Each	1 8 0	6
23	Teakwood shelf plank, $\frac{1}{2}$ " thick	87	S.ft.	1 8 0	131
24	Flooring with 9" square Mangalore tiles over 3" concrete and cement pointing.	4.29	Sqr.	35 0 0	150
25	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	4.61	"	40 0 0	184
26	Constructing cisterns	2	Each	5 0 0	10
27	Clearing site	Lump	sum		10
Total					4,639
<i>Latrine.</i>					
1	Earthwork excavation	4	C.yd.	0 4 0	1
2	Burnt brick in clay	362	C.ft.	0 8 6	78
3	Coping with burnt brick in mortar and plastering, complete.	40	R.ft.	0 6 0	15
4	Plastering with mortar	4.32	Sqr.	4 0 0	17
5	Tarring	1.14	"	2 0 0	2
6	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	0.63	"	40 0 0	25
Total					138
Total Rs. for building and latrine					4,777
Compensation for lands to be acquired					2,247
Total					5,024
Contingencies at 5%					251
Grand Total					5,275

L. A. H. WINCKLER,
Executive Engineer.

SPECIAL DIVISION, MYSORE.

Notification dated 15th October 1927.

Notice is hereby given that a sum of Rs. 7-10-5, being the amount of interest on the security furnished by Sub-Overseer G. Narayanaswamy and outstanding in his Pass Book No. 6434 as due to him, remains unclaimed. If no claim is made within three months from the date of the issue of this notice in the Gazette, the amount will be forfeited to Government.

V. V. KARVE,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 29th September 1927.

The attention of the public is invited to the notice calling for tenders, for "Constructing Barr Sepoys' quarters at Honnali, see pages 787 and 788, Part VI of the *Mysore Gazette* dated 29th September 1927.